

OXBOW ROAD 6-INCH WATERLINE REPLACEMENT PROJECT (F 3/10 ROAD TO F 1/2 ROAD) SCHEDULE OF PRICES
Revised per Addendum No. 1

Item	Description	Unit	Estimated Quantity	Unit Price	Total Price
1	Mobilization, Bonds, Permits, Insurance	LS	1		
2	Asbestos Pipeline Removal and Disposal	LF	1,000		
3	Pipeline Trench Excavation and Backfill (Trench Detail, Sheet 7)				
	a. Class I (asphalt roads and driveways)	LF	1,000		
4*	Select Backfill Material as Directed by Engineer - Includes Removal and Disposal of Unsuitable Material from Required Excavation.				
	a. Type A Material (aggregate base course)	Ton	250	\$ 26.00	\$ 6,500.00
	b. Type E Material (approved pit run)	Ton	250	\$ 21.50	\$ 5,375.00
	c. 1 1/2" Screened Rock	Ton	100	\$ 27.00	\$ 2,700.00
5	Pipeline Trench Surface Restoration (Trench Detail, Sheet 10)				
	a. Asphalt Pavement (4-inch thickness) (Includes striping per Mesa County Specifications)	Ton	100		
	b. Asphalt Pavement Mill & Overlay (Includes striping per Mesa County Specifications)	Ton	80.0		
	c. Class D: Concrete Driveways, Sidewalks, Curbs and Gutter	LF	60		
6	Pipeline and Fittings, in place - Includes all pipe, valves, fittings and appurtenances. DI Fittings and accessories shall be DOMESTIC.				
	6-inch C900 DR-18 PVC Pipe	LF	1,000		
7	Meter Service Connections - Includes all material, labor, and equipment necessary to relocate and connect to either existing water meter service lines or new water meter yokes. Includes surface restoration.				
	b. 3/4" service line (Both sides)	EA	20		
8	New Fire Hydrant Installation- Includes trench excavation, backfill (Class I), surface restoration (asphalt), new hydrant, pipe, valve, fittings, and restraints. DI Fittings and accessories shall be DOMESTIC. (STA 12+36, 28+04, 63+00), (Detail B, Sheet 10), (Grand Junction Fire Dept Hydrant)	EA	2		
9	Traffic Control - Adder for Flaggers as required for a portion of this work to manage one-way traffic as needed.	Day	15		
10	Potholing as Directed by the Engineer - Includes all equipment and labor for subsurface investigation.	HR	20		
Total					

* Item 4 (Engineer Directed Backfill) will be paid at the unit price listed in the Schedule of Prices.

This Bid was prepared for the below listed Contractor.

CONTRACTOR

Name:

Title:

Signature:

Date:
